

Green Communities Ground-Mounted Solar PV Overlay District By-law dated February 17, 2010

Amend the Town of Kingston Zoning By-Laws by adding a new Section 4.17. Large-Scale Ground-Mounted Solar Photovoltaic Overlay District as shown in a document entitled Green Communities Ground-Mounted Solar PV Overlay District By-law dated February 17, 2010 to comply with the Green Communities Act and allow ground mounted photovoltaic installations to be allowed under site plan approval (by right) and be subject to expedited permitting and by amending the Town of Kingston Zoning Map to include in the Solar PV Overlay District consisting of Assessor's Map 75, Lot 11 and Map 66 Lot 50 and by adding to the list of Zoning Districts in Section 3.1. of the Zoning By-Laws the following district: "Solar PV Overlay District".

4.17. Large-Scale Ground-Mounted Solar Photovoltaic Installations Overlay District

4.17.1.0. Purpose The purpose of this bylaw is to promote the creation of new large-scale ground-mounted solar photovoltaic installations by providing standards for the placement, design, construction, operation, monitoring, modification and removal of such installations that address public safety, minimize impacts on scenic, natural and historic resources and to provide adequate financial assurance for the eventual decommissioning of such installations.

The provisions set forth in this section shall apply to the construction, operation, and/or repair of large-scale ground-mounted solar photovoltaic installations.

4.17.1.1. Applicability This section applies to large-scale ground-mounted solar photovoltaic installations proposed to be constructed after the effective date of this section. This section also pertains to physical modifications that materially alter the type, configuration, or size of these installations or related equipment.

4.17.2.0. Definitions

4.17.2.1. As-of-Right Siting: As-of-Right Siting shall mean that development may proceed without the need for a special permit, variance, amendment, waiver, or other discretionary approval. As-of-right development may be subject to site plan review to determine conformance with local zoning ordinances or bylaws. Projects cannot be prohibited, but can be reasonably regulated by the inspector of buildings, building commissioner or local inspector, or if there is none in a town, the board of selectmen, or person or board designated by local ordinance or bylaw.

4.17.2.2. Building Inspector: The inspector of buildings, building commissioner, or local inspector, or person or board designated by local ordinance or bylaw charged with the enforcement of the zoning ordinance.

4.17.2.3. Building Permit: A construction permit issued by an authorized building inspector; the building permit evidences that the project is consistent with the state and federal building codes as well as local zoning bylaws, including those governing ground-mounted large-scale solar photovoltaic installations.

4.17.2.4. Designated Location: The locations designated by Town Meeting, in accordance with Massachusetts General Laws Chapter 40A, section 5, where ground - mounted large scale solar photovoltaic installations may be sited as-of right. Said locations are shown on a Zoning Map of Kingston, Massachusetts dated December 17, 1993 revised through **April XX, 2010** pursuant to Massachusetts General Laws Chapter 40A Section 4. This map is hereby made a part of this Zoning Bylaw and is on file in the Office of the Town Clerk.

4.17.2.5. Large-Scale Ground-Mounted Solar Photovoltaic Installation: A solar photovoltaic system that is structurally mounted on the ground and is not roof-mounted, and has a minimum nameplate capacity of 250 kW DC.

4.17.2.6. On-Site Solar Photovoltaic Installation: A solar photovoltaic installation that is constructed at a location where other uses of the underlying property occur.

4.17.2.7. Rated Nameplate Capacity: The maximum rated output of electric power production of the Photovoltaic system in Direct Current (DC).

4.17.2.8. Site Plan Review: review by the Site Plan Review Authority to determine conformance with local zoning ordinances or bylaws.

4.17.2.9. Site Plan Review Authority: For purposes of this bylaw, Site Plan Review Authority refers to the body of local government designated as such by the municipality

4.17.2.10. Solar Photovoltaic Array: an arrangement of solar photovoltaic panels.

4.17.2.11. Zoning Enforcement Authority: The person or board charged with enforcing the zoning ordinances or bylaws.

4.17.3.0. General Requirements for all Large Scale Solar Power Generation Installations
The following requirements are common to all solar photovoltaic installations to be sited in designated locations.

4.17.3.1. Compliance with Laws, Ordinances and Regulations

The construction and operation of all large scale solar photovoltaic installations shall be consistent with all applicable local, state and federal requirements, including but not limited to all applicable safety, construction, electrical, and communications requirements. All buildings and fixtures forming part of a solar photovoltaic installation shall be constructed in accordance with the State Building Code.

4.17.3.2. Building Permit and Building Inspection

No large scale solar photovoltaic installation shall be constructed, installed or modified as provided in this section without first obtaining a building permit.

4.17.3.3. Fees

The application for a building permit for a large scale solar photovoltaic installation must be accompanied by the fee required for a building permit.

4.17.3.4. Renewable or alternative energy research and development facilities, and renewable or alternative energy manufacturing facilities, subject to Site Plan Review by the Planning Board, pursuant to Section 7.3 and 4.17.3.4. Site Plan Review and subject to the dimensional requirements of Section 4.17.3.8. Dimension and Density Requirements. Said Site Plan Approval shall be an "expedited" application and permitting process under which said facilities may be sited within one (1) year from the date of initial application to the date of final approval by the Planning Board.

4.17.3.4. Site Plan Review

Ground-mounted large scale solar photovoltaic installations with 250 kW or larger of rated nameplate capacity shall undergo site plan review by the Site Plan Review Authority prior to construction, installation or modification as provided in this section.

4.17.3.4.1. General

All plans and maps shall be prepared, stamped and signed by a Professional Engineer licensed to practice in Massachusetts.

4.17.3.4.2. Required Documents

Pursuant to the site plan review process, the project proponent shall provide the following documents:

- (a) A site plan showing:
 - i. Property lines and physical features, including roads, for the project site;
 - ii. Proposed changes to the landscape of the site, grading, vegetation clearing and planting, exterior lighting, screening vegetation or structures;
 - iii. Blueprints or drawings of the solar photovoltaic installation signed by a Professional Engineer licensed to practice in the Commonwealth of Massachusetts showing the proposed layout of the system and any potential shading from nearby structures
 - iv. One or three line electrical diagram detailing the solar photovoltaic installation, associated components, and electrical interconnection methods, with all National Electrical Code compliant disconnects and overcurrent devices;
 - v. Documentation of the major system components to be used, including the PV panels, mounting system, and inverter;
 - vi. Name, address, and contact information for proposed system installer;
NEED RFP TO ID INSTALLER
 - vii. Name, address, phone number and signature of the project proponent, as well as all co-proponents or property owners, if any; **NEED RFQ TO ID PROPONENT**
 - viii. The name, contact information and signature of any agents representing the project proponent; and
- (b) Documentation of actual or prospective access and control of the project site (see also Section 3.5);

- (c) An operation and maintenance plan (see also Section 3.6);
- (d) Zoning district designation for the parcel(s) of land comprising the project site (submission of a copy of a zoning map with the parcel(s) identified is suitable for this purpose);
- (e) Proof of liability insurance; and
- (f) Description of financial surety that satisfies Section 3.12.3.

The Site Plan Review Authority may waive documentary requirements as it deems appropriate.

4.17.3.5. Site Control

The project proponent shall submit documentation of actual or prospective access and control of the project site sufficient to allow for construction and operation of the proposed solar photovoltaic installation.

4.17.3.6. Operation & Maintenance Plan

The project proponent shall submit a plan for the operation and maintenance of the large-scale ground-mounted solar photovoltaic installation, which shall include measures for maintaining safe access to the installation, storm water controls, as well as general procedures for operational maintenance of the installation.

4.17.3.7. Utility Notification

No large- scale ground –mounted solar photovoltaic installation shall be constructed until evidence has been given to the Site Plan Review Authority that the utility company that operates the electrical grid where the installation is to be located has been informed of the solar photovoltaic installation owner or operator’s intent to install an interconnected customer-owned generator. Off-grid systems shall be exempt from this requirement.

4.17.3.8. Dimension and Density Requirements

4.17.3.8.1. Setbacks

For large - scale ground-mounted solar photovoltaic installations, front, side and rear setbacks shall be as follows:

- (a) Front yard: The front yard depth shall be at least 10 feet; provided, however, that where the lot abuts a Conservation-Recreation or Residential district, the front yard shall not be less than 50 feet.
- (b) Side yard. Each side yard shall have a depth at least 15 feet; provided, however, that where the lot abuts a Conservation-Recreation or Residential district, the front yard shall not be less than 50 feet.
- (c) Rear yard. The rear yard depth shall be at least 25 feet; provided, however, that where the lot abuts a Conservation-Recreation or Residential district, the front yard shall not be less than 50 feet.

4.17.3.8.2. Appurtenant Structures

All appurtenant structures to large- scale ground-mounted solar photovoltaic installations shall be subject to reasonable regulations concerning the bulk and height

of structures, lot area, setbacks, open space, parking and building coverage requirements. All such appurtenant structures, including but not limited to, equipment shelters, storage facilities, transformers, and substations, shall be architecturally compatible with each other. Whenever reasonable, structures should be shaded from view by vegetation and/or joined or clustered to avoid adverse visual impacts.

4.17.3.9. Design Standards

4.17.3.9.1. Lighting

Lighting of solar photovoltaic installations shall be consistent with local, state and federal law. Lighting of other parts of the installation, such as appurtenant structures, shall be limited to that required for safety and operational purposes, and shall be reasonably shielded from abutting properties. Where feasible, lighting of the solar photovoltaic installation shall be directed downward and shall incorporate full cut-off fixtures to reduce light pollution.

4.17.3.9.2. Signage

Signs on large- scale ground-mounted solar photovoltaic installations shall comply with a municipality's sign bylaw. A sign consistent with a municipality's sign bylaw shall be required to identify the owner and provide a 24-hour emergency contact phone number.

Solar photovoltaic installations shall not be used for displaying any advertising except for reasonable identification of the manufacturer or operator of the solar photovoltaic installation.

4.17.3.9.3. Utility Connections

Reasonable efforts, as determined by the Site Plan Review Authority, shall be made to place all utility connections from the solar photovoltaic installation underground, depending on appropriate soil conditions, shape, and topography of the site and any requirements of the utility provider. Electrical transformers for utility interconnections may be above ground if required by the utility provider.

4.17.3.10. Safety and Environmental Standards

4.17.3.10.1. Emergency Services

The large scale solar photovoltaic installation owner or operator shall provide a copy of the project summary, electrical schematic, and site plan to the local fire chief. Upon request the owner or operator shall cooperate with local emergency services in developing an emergency response plan. All means of shutting down the solar photovoltaic installation shall be clearly marked. The owner or operator shall identify a responsible person for public inquiries throughout the life of the installation.

4.17.3.10.2. Land Clearing, Soil Erosion and Habitat Impacts

Clearing of natural vegetation shall be limited to what is necessary for the construction, operation and maintenance of the large – scale ground-mounted solar

photovoltaic installation or otherwise prescribed by applicable laws, regulations, and bylaws.

4.17.3.11. Monitoring and Maintenance

4.17.3.11.1 Solar Photovoltaic Installation Conditions

The large - scale ground-mounted solar photovoltaic installation owner or operator shall maintain the facility in good condition. Maintenance shall include, but not be limited to, painting, structural repairs, and integrity of security measures. Site access shall be maintained to a level acceptable to the local Fire Chief and Emergency Medical Services. The owner or operator shall be responsible for the cost of maintaining the solar photovoltaic installation and any access road(s), unless accepted as a public way.

4.17.3.11.2. Modifications

All material modifications to a solar photovoltaic installation made after issuance of the required building permit shall require approval by the Site Plan Review Authority.

4.17.3.12. Abandonment or Decommissioning

4.17.3.12.1. Removal Requirements

Any large- scale ground-mounted solar photovoltaic installation which has reached the end of its useful life or has been abandoned consistent with Section 3.12.2 of this bylaw shall be removed. The owner or operator shall physically remove the installation no more than 150 days after the date of discontinued operations. The owner or operator shall notify the Site Plan Review Authority by certified mail of the proposed date of discontinued operations and plans for removal. Decommissioning shall consist of:

- (a) Physical removal of all large- scale ground-mounted solar photovoltaic installations, structures, equipment, security barriers and transmission lines from the site.
- (b) Disposal of all solid and hazardous waste in accordance with local, state, and federal waste disposal regulations.
- (c) Stabilization or re-vegetation of the site as necessary to minimize erosion. The Site Plan Review Authority may allow the owner or operator to leave landscaping or designated below-grade foundations in order to minimize erosion and disruption to vegetation.

4.17.3.12.2. Abandonment

Absent notice of a proposed date of decommissioning or written notice of extenuating circumstances, the solar photovoltaic installation shall be considered abandoned when it fails to operate for more than one year without the written consent of the Site Plan Review Authority. If the owner or operator of the large- scale ground-mounted solar photovoltaic installation fails to remove the installation in accordance with the requirements of this section within 150 days of abandonment or the proposed date of

decommissioning, the town may enter the property and physically remove the installation.

4.17.3.12.3. Financial Surety

Proponents of large-scale ground-mounted solar photovoltaic projects shall provide a form of surety, either through escrow account, bond or otherwise, to cover the cost of removal in the event the town must remove the installation and remediate the landscape, in an amount and form determined to be reasonable by the Site Plan Review Authority, but in no event to exceed more than 125 percent of the cost of removal and compliance with the additional requirements set forth herein, as determined by the project proponent. Such surety will not be required for municipally- or state-owned facilities. The project proponent shall submit a fully inclusive estimate of the costs associated with removal, prepared by a qualified engineer. The amount shall include a mechanism for calculating increased removal costs due to inflation.